



STOP CONCRETE CURB & GUTTER 3' SHORT OF CATCH BASIN CASTING, SET CASTING TO BINDER COURSE GRADE AND INSTALL TEMPORARY ASPHALT CURB & GUTTER.

AT TIME OF FINAL ASPHALT SURFACING, ADJUST CASTING TO FINAL GRADE AND REPLACE ASPHALT CURB & GUTTER WITH CONCRETE.

36" No.4 EPOXY COATED REBAR SHALL BE PLACED IN THE CURB HEAD CENTERED ON THE CASTING.



City of Oak Creek
Department of Public Works

Drawn By: K. SEUFZER

Scale: N.T.S.

Appv. By: W. ST. JOHN

Date: 12/5/03 (Revised)

INTERIM (BINDER GRADE) CURB INLET

RO-8