

Weatherly Drive Reconstruction Project

W. Weatherly Drive spanning from Wilding Drive to Waring Drive has always been considered a temporary roadway. It has served as a second access to the apartments and Willow Heights subdivision through the park, and was planned to be removed when the proposed bridge connecting Wildwood Drive was finally constructed. With the proposed Wildwood bridge having been removed from the City's officially mapped street map by Council action, it has become necessary to make Weatherly Drive a permanent roadway. The W. Weatherly Drive reconstruction project will replace the existing asphalt roadway with a curbed concrete pavement and sidewalk. The road will be elevated above the regional floodplain and a 52-foot wide Conspan culvert across the North Branch of Oak Creek will be installed as well as two 8'x5' box culverts. The new road was designed to pass flood flows without overtopping or increase flood elevations both up and downstream. The construction contract was awarded to BCF Construction Corp. The road closure schedule has yet to be determined, but preliminary work will start this fall with the bulk of the construction being done in 2015 with completion by October 30, 2015.



1 in = 300 ft

